

PROPOSAL

Hannula Landscaping And Irrigation, Inc.

28131 Quails Nest Lane
Bonita Springs, FL 34135-6932
Phone 239-992-2210 - Fax 239-498-6818

DATE	September 28, 2015
JOB	GG MSTU West Entry Sign
Location	Naples, FL

WE HEREBY SUBMIT ESTIMATES FOR THE ABOVE NAMED PROJECT IN ACCORDANCE WITH THE SPECIFICATIONS OF THIS PROPOSAL. ALL LABOR AND MATERIALS WILL BE FURNISHED IN COMPLETE ACCORDANCE WITH THE SPECIFICATION OF THIS PROPOSAL. THIS PROPOSAL SHALL BE VALID FOR A PERIOD OF NINETY (90) DAYS.

Landscape	55,450.00
Site Work	2,200.00
Sod	3,904.92
TOTAL PROPOSED COST	\$ 61,554.92

WARRANTY

All plant material is guaranteed to meet specifications as stated herein. Any alteration or deviation from said specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above the estimate. Shrubs and ground covers are guaranteed 90 days, shade trees and palms 180 days, and sod 30 days. The Contractor will replace any plant that dies or is not established during said warranty period if cause is due to negligence or poor workmanship by the Contractor. Maintenance of the planting and sod after the date of acceptance to the end of the guarantee period shall be by the Owner.

The irrigation system on the materials and workmanship is guaranteed for a period of 12 months from the date of installation, excluding damages by third parties, theft after installation, or damage or loss due to an act of nature.

Contractor is not responsible for any cut cables, lines, pipes, or wires that cannot be accurately located and marked by No Cut personnel. Alterations or deviations from the above specifications will be executed only upon written orders and will become extra charges over and above the estimate.

ACCEPTANCE OF PROPOSAL

The above prices, specifications and conditions are hereby accepted. You are authorized to do the work as specified.

Date	Hannula Landscaping, Inc.
-------------	----------------------------------

**HANNULA LANDSCAPING & IRRIGATION, INC.
 BID COST**

PROJECT GG MSTU West Entry Sign
DATE September 28, 2015

ITEM	QTY	DESCRIPTION	SPECIFICATIONS	TOTAL COST
		Per Plans Dated: 2/23/12		
		Large Palms 16-20"cal		
RE	4	Royal Palm	10'ct, 18"min cal (6'gw)	
		Sabal Palm		
SP	2	Sabal Palm	10'booted	
SP	38	Sabal Palm	15'ct	
SP	2	Sabal Palm	18'ct	
		Small Tree 4-6"cal		
QV	7	Catherdrai Live Oak	18-20x10x4-5"cal	
QV1	10	Catherdrai Live Oak	18-20x10x4-5"cal	
		Small Tree 1.5-3"cal		
Jl	3	Jatropha	6x6, 3stem, B&B	
TC	2	Gold Trumpet Tree	12-14x7x3" cal, B&B	
		15g		
SRC	17	Silver Saw Palmetto	15g, 36", full	
		14-22" available		
		7g		
SRC	52	Silver Saw Palmetto	7g, 24"	
		12-16" available		
		3g		
HP	35	Dwarf Firebush	3g, 24"	
HL	108	Splder Lily	3g, 18"	
SPB	65	Sand Cordgrass	3g, 24"	
		1g		
LML	44	Trailing Lantana Lavendar	1g, 8"x12"	
LMW	44	Trailing Lantana White	1g, 8"x12"	
TV	290	Society Garlic	1g, 6"x6"	
DT	74	Blueberry Flax Lily	1g, 14"ht	
		Mulch		
	108	Eucalyptus	cubic yard allowance	
	4.15	Eucalyptus Mulch Optional	cubic yard allowance	
		Soil		
	88	Planting Soil	cubic yard allowance	
		TOTAL LANDSCAPE COST		
				55,450.00
		Site Work		
	1.00	Misc. Site Work	allowance	
		TOTAL SITE WORK		
				2,200.00
		Sod		
	10,847	Floratan Sod	square ft allowance	
		TOTAL SOD COST		
				3,904.92
		TOTAL BID COST		
				61,554.92

LANDSCAPE NOTES:

*REMOVAL OF EXOTICS, SITE PREPARATION AND GRADING ARE TO BE PROVIDED BY OTHERS UNLESS NOTED WITHIN THE BID COST.

*SOD REMOVAL IS NOT INCLUDED UNLESS NOTED WITHIN THE BID COST.

*ALL MATERIAL PRICED WITH FLORIDA #1 GRADE STANDARDS UNLESS OTHERWISE DENOTED AS SPECIMEN OR FLORIDA FANCY. IF MATERIAL IS NOT READILY AVAILABLE WITH FLORIDA #1 GRADE STANDARDS AT THE TIME OF INSTALLATION, ADDITIONAL COSTS SHALL APPLY TO UPGRADE MATERIAL TO FLORIDA FANCY GRADE STANDARDS OR A SUBSTITUTION OF EQUAL OR LESSER VALUE WILL BE REQUIRED UNDER THE DIRECTION AND APPROVAL OF THE LANDSCAPE ARCHITECT.

*ALL LANDSCAPE MATERIAL AND SOD MUST BE IRRIGATED BY AN 100% OPERATIONAL IRRIGATION SYSTEM IN ORDER TO WARRANTY MATERIAL INSTALLED.

*RELOCATION OF ANY MATERIAL - WARRANTY SHALL NOT BE PROVIDED FOR RELOCATED MATERIAL.

*THIS CONTACTOR IS NOT RESPONSIBLE FOR MATERIAL DETERIORATING DUE TO MANDATED WATER RESTRICTIONS.

*SUBSURFACE CONDITIONS CANNOT BE DETERMINED AT THE TIME OF ESTIMATING UNLESS THE OWNER REQUIRES TEST PITS TO BE DUG. CONTRACTOR DOES NOT GUARANTEE ADEQUATE DRAINAGE WITHOUT DETERMINING THE SUBSURFACE CONDITIONS BY DIGGING TEST PITS. TEST PITS ARE NOT INCLUDED, BUT AVAILABLE UPON REQUEST AT ADDITIONAL COSTS TO BE DETERMINED ON A JOB TO JOB BASIS.

IRRIGATION NOTES:

*WATER SOURCE, WATER METER, BACKFLOW PREVENTER, IRRIGATION WELL, CONCRETE PAD FOR EQUIPMENT, WATER USE PERMIT AND ELECTRICAL SERVICE FOR IRRIGATION EQUIPMENT ARE TO BE PROVIDED BY OTHERS UNLESS NOTED WITHIN THE BID COST.

*IF IRRIGATION WATER IS SUPPLIED BY WELL, THE DEPTH OF THE WELL IS ESTIMATED AND DISCLAIMED WITHIN THE BID COST. DEPTHS AND CASING REQUIRED IN ADDITION TO THOSE DISCLAIMED WITHIN THE BID COST SHALL BE PROVIDED AT AN ADDITIONAL COST.

*OWNER TO GUARANTEE ADEQUATE PRESSURE FOR A 100% OPERATIONAL IRRIGATION SYSTEM. THE ESTIMATED REQUIRED GALLONS PER MINUTE AND STATIC PRESSURE RATING AT THE METER IS PROVIDED WITHIN THE BID COST. FLOW RATES THAT EXCEED THOSE DISCLAIMED OR PRESSURE RATINGS THAT DO NOT MEET REQUIREMENTS DISCLAIMED WITHIN BID COST SHALL REQUIRE A REDESIGN OF THE IRRIGATION SYSTEM. COSTS RELATING TO FLOW AND PRESSURE DISCREPANCIES ARE TO BE PROVIDED AT AN ADDITIONAL COST.

*CONTRACTOR DOES NOT GUARANTEE QUALITY OF WATER.

*UNLESS NOTED, IRRIGATION TRENCHES SHALL BE DUG AT A ONE FOOT DEPTH FOR LATERAL PIPE AND A TWO FOOT DEPTH FOR MAIN LINE UNDER CONSTANT PRESSURE.

*IF ROCK IS FOUND TOO LARGE FOR TRENCHER, THE OWNER WILL BE RESPONSIBLE FOR ADDITIONAL COSTS.

*SUBSURFACE CONDITIONS CANNOT BE DETERMINED AT THE TIME OF ESTIMATING UNLESS THE OWNER REQUIRES TEST TRENCHES TO BE DUG. CONTRACTOR DOES NOT GUARANTEE TRENCHES CAN BE DUG AT REQUIRED DEPTHS WITHOUT DETERMINING THE SUBSURFACE CONDITIONS BY DIGGING TEST TRENCHES. TEST TRENCHES ARE NOT INCLUDED, BUT AVAILABLE UPON REQUEST AT ADDITIONAL COSTS TO BE DETERMINED ON A JOB TO JOB BASIS.

GENERAL NOTES:

*SUBCONTRACTOR SHALL FURNISH ALL ITEMS SPECIFIED IN SCHEDULE OF VALUES. CONTRACTOR/ OWNER SHALL BE SOLELY RESPONSIBLE FOR THE ACCURATENESS OF THE PLANS AND SPECIFICATIONS AND SHALL RELEASE HOLD HARMLESS SUBCONTRACTOR FROM ANY DAMAGES RESULTING FROM INADEQUATE, INACCURATE, OR VAGUE INFORMATION SUPPLIED BY THE CONTRACTOR/OWNER.