

400- The completion of materials installed for gas distribution. Check for pipe protection plates as required and pressure test required if other than 30# label with the test pressure, date, time and technician.

