

201- Completed after the roof, framing, fire blocking, and bracing is in place and all water, soil, waste and vent piping is complete, and prior to the installation of wall or ceiling membranes. All piping required to be tested per FBC Building Section 110, FBC Plumbing Section 312 and FBC Residential Section P2503.

